

NOZZLE SCHEDULE							
MARK	QTY	SIZE	RATING LBS	FLG/CPLG TYPE	WALL THK	DESCRIPTION	REF DWG
A	1	1.5"	2500#	RFVN	160	DUTLET WITH RISER PIPE	07
B	1	1.5"	2500#	RFVN	160	INLET WITH DOWN PIPE	07
C	1	1.5"	2500#	RFVN	160	TOP NOZ WITH BLIND	08
E	1	2"	2500#	RFVN	160	INSPECTION WITH BLIND	08
F	1	2"	2500#	RFVN	160	INSPECTION WITH BLIND	08
G	1	2"	300#	RFVN	80	JACKET INLET	04
H	2	1.5"	300#	RFVN	80	JACKET DUTLETS	04
J	1	1/2"	3000#	CPLG	N/A	JACKET VENT WITH PLUG	04
K	2	6"	N/A	N/A	40	SKIRT SLEEVES (VIEW)	05


TANK SUPPORT/FOUNDATION NOTE

TANK SUPPORT TO BE CONTINUOUSLY AND UNIFORMLY SUPPORTED WITH NO DIFFERENTIAL DEFLECTION OR SETTLEMENT. THIS INCLUDES, BUT IS NOT LIMITED TO SKIRTS, FLAT BOTTOMS, BASE PLATES, AND SADDLE SUPPORTS. IRREGULARITIES IN SETTLEMENT/DEFLECTION MAY LEAD TO AN UNBALANCING OF THE LOADING CONDITIONS ASSUMED IN THE DESIGN AND POSSIBLY TO SERIOUS DISTORTION OF IMPORTANT ELEMENTS OF THE TANK.

SUPPORT STRUCTURES TO BE LEVEL WITHIN $\pm .1/8"$ IN ANY 30 FEET OF CIRCUMFERENCE AND WITHIN $\pm .1/4"$ IN THE TOTAL CIRCUMFERENCE MEASURED FROM THE AVERAGE ELEVATION.

<input type="checkbox"/>				
<input type="checkbox"/>				
<input type="checkbox"/>				
<input checked="" type="checkbox"/>	9/17 2014	JPLEAS	FIRST ISSUE	10/2/14
REV.	DATE	BY	REVISION DESCRIPTION	CHECKED
				APPROVED

THIS DRAWING IS THE PROPERTY OF ENERFAB INC. IT IS TO BE USED ONLY IN CONNECTION WITH THE PERFORMANCE OF WORK BY ENERFAB, INC. NO PARTS OR PORTIONS OF THIS DRAWING ARE TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS WITHOUT PERMISSION IN WRITING FROM ENERFAB, INC. VIOLATION OF THESE PROVISIONS IS CONSIDERED A BREACH OF CONTRACT AND WILL BE PROSECUTED TO THE FULL EXTENT OF THE LAW.



EXCELLENCE THROUGH EXECUTION
 4955 SPRING GROVE AVENUE
 CINCINNATI, OHIO 45232-1991

CUSTOMER & LOCATION	PATRIOT FUELS BIDDLESEL, LLC ANNAWAN, IL
PROJECT INFORMATION	(1) 600 GALLON HIGH PRESSURE BIDDLESEL REACTOR P.D. NUMBER 008526 EQ. NUMBER C-408
DRAWING TITLE	GENERAL ASSEMBLY
PROJECT NO.:	1410086
DRAWING NO.:	1410086-01
REV.	<input checked="" type="radio"/>

