



DETAIL "A"
TYPICAL

- NOTES:
- HEADS & REMOVABLE TUBE TO BE STAMPED WITH VESSEL SERIAL NUMBER
 - PRODUCT NET VOLUME - 910 CU. IN.
 - JACKET VOLUME - 2000 CU. IN.
 - APPROXIMATE WEIGHT: 1150 LBS.

USE THIS NUMBER
90294E
WHEN CORRESPONDING
OR ORDERING PARTS

DESIGN DATA	CODE: LATEST INSPT. MEG	S.M.E.P.V. CODE SECT. VIII DIV.1 STAMP'G UM	HYDRO TEST	CORR. ALLOW
SIDE	MAWP / MDMT			
TUBE	400 PSI @ 375°F -20°F @ 400PSI		600 PSI	NONE
JACKET	150 PSI @ 375°F -20°F @ 150PSI		225 PSI	NONE

CERA/CERA/BUNA	17-7PH NI CR PL .004	4 11/16" 304 SS
SEALS	BLADE & TUBE MATERIAL	SHAFT DIA. & MATERIAL

CHERRY-BURRELL
AMCA INTERNATIONAL
PROCESS EQUIPMENT DIVISION

FOR CYLINDER ASSEMBLY 6 X 72 MED. DUTY BWS

DRAWN BY: J.E.M.
ENGR. CHECK BY: DHB
DATE: 12-28-90
SERIAL NO.:
SIZE: D

DRAWING NO. 906229

REV	BY	DESCRIPTION	DATE
1	RHB	ADDED SPIRAL, CAN. & PACKING.	2/27/91